No.	Items of work	Unit	Rate	Quantity	Cost
	SLUICE AT R. L. 50·00.		Rs. a. p.		
1	Earthwork cutting	C.yd.		89	
2	Concrete in surki mortar	C.ft.		119	
3	Burnt brick in surki mortar	„		321	
4	Burnt stone slabs 6" thick	S.ft.		196	
5	Boring holes in orifice slabs	No.		3	
6	Plastering with surki mortar	Sqr.		5·46	
7	Providing plug and rod	Lump sum		...	
8	Refilling the cut with watering and tamping ...	C.yd.		36	
	WASTE WEIR 90' LONG AT R. L. 55·00.				
1	Earthwork excavating and using the same to flank bund with watering and tamping.	C.yd.		325	
2	Excavation in rock	„		9	
3	Concrete in surki mortar	C.ft.		251	
4	Burnt brick in surki mortar	„		2,337	
5	Burnt stone slabs 6" thick	S.ft.		317	
6	Plastering with mortar	S.qrs.		19·42	
7	Rough stone work new	C.ft.		153	
8	Jelly filling below apron	„		117	
9	Providing peir slabs 3'×1'	No.		10	
10	Providing joggle joints	„		15	
	Total ...	...	...	...	...
	Total bund, sluice and weir ...	...	...	...	...
	Contingencies ...	...	...	...	...
	Grand Total ...	...	...	...	...

N. LAKSHMINARASIMHIAYA,
Executive Engineer.

THE BANK OF MYSORE, LIMITED, BANGALORE.

Statement of the affairs of the Bank of Mysore, Limited, for the week ending 31st July 1930, published under Article 141 of the Articles of Association.

LIABILITIES		Rs.	ASSETS		Rs.
To Capital Receipts	...	20,00,000	By Cash in Hand and at Bankers		17,99,490
Reserve Funds	...	18,00,000	„ Loans & Cash Credit Accounts		1,81,54,734
Public and other Deposits	..	1,99,22,826	„ Bills discounted	...	4,67,317
„ Sundries	..	2,07,359	„ Investments	...	18,34,717
			„ Balance at Agencies	...	16,082
(Annas and pies omitted.)			„ Dead Stock	...	5,74,162
			„ Sundries	..	83,683
Total	... Rs.	2,39,30,185	Total	.. Rs.	2,39,30,185

BANGALORE,
Dated 5th August 1930.

P. W. O'BRIEN,
Manager.